

Watershed Inventory Report

Phase 1 of the Watershed Improvement Plan

**BOROUGH OF ROOSEVELT
MONMOUTH COUNTY**

Date Report: December 31, 2025

Permit Number: NJG0152889

Stormwater Program Coordinator: Carmela Roberts, P.E., C.M.E., C.P.W.M.

NJPE License #NJ24GE034419000

Table of Contents

ACRONYMS & DEFINITIONS	3
LIST OF FIGURES	5
LIST OF TABLES	5
ACKNOWLEDGEMENTS	6
REGIONAL COLLABORATION	6
INTRODUCTION	7
PUBLIC PARTICIPATION	10
STORMWATER OUTFALL(S)	11
<i>Stormwater Outfalls Owned/Operated by Permittee</i>	11
<i>Receiving Surface Waters</i>	11
<i>Water Quality Classifications</i>	11
STORMWATER INTERCONNECTION(S)	14
<i>Interconnections from the Borough's MS4 into another entity's storm or sanitary sewer system</i>	14
<i>Interconnection(s) into the permittee's MS4 from another entity</i>	14
DRAINAGE AREA(S) FOR STORMWATER OUTFALLS AND STORMWATER INTERCONNECTIONS	17
<i>Storm Drain Inlets</i>	17
<i>MS4 Outfall Drainage Areas</i>	17
<i>Drainage area of interconnection(s) from the permittee to another entity</i>	17
TMDLS AND WATER QUALITY IMPAIRMENTS	19
OVERBURDENED COMMUNITIES	22
IMPERVIOUS AREA	24
NON-MUNICIPALLY OWNED OR OPERATED STORMWATER FACILITIES (FOR TIER A PERMITTEES ONLY)	26
CONCLUSION	29
REFERENCES	30
APPENDIX	30

Acronyms & Definitions

1. Acronyms

- i. "BMP" – Best Management Practice
- ii. "DO" – Dissolved Oxygen
- iii. "EPA" – U.S. Environmental Protection Agency
- iv. "GIS" – Geographic Information System
- v. "HUC 14" – Hydrologic Unit Code 14
- vi. "MS4" – Municipal Separate Storm Sewer System
- vii. "MTD" – Manufactured Treatment Device
- viii. "NJPDES" – New Jersey Pollutant Discharge Elimination System
- ix. "NJ-WET" – New Jersey Watershed Evaluation Tool
- x. "TDS" – Total Dissolved Solids
- xi. "TMDL" – Total Maximum Daily Load
- xii. "TSS" – Total Suspended Solids
- xiii. "WIP" – Watershed Improvement Plan

2. Definitions

- i. "**HUC 14**" or "hydrologic unit code 14" means an area within which water drains to a particular receiving surface water body, also known as a subwatershed, which is identified by a 14-digit hydrologic unit boundary designation, delineated within New Jersey by the United States Geological Survey. (see N.J.A.C. 7:9B).
- ii. "**Municipal separate storm sewer**" (or MS4 conveyance) means a conveyance or system of conveyances (including roads with drainage systems, municipal streets, catch basins, curbs, gutters, ditches, manmade channels, or storm drains) as defined in more detail at N.J.A.C. 7:14A-1.2.
- iii. "**Outfall**" means any point source which discharges directly to waters of the United States and does not include open conveyances connecting two municipal separate storm sewers, or pipes, tunnels or other conveyances which connect segments of the same stream or other waters of the United States and are used to convey waters of the United States.
- iv. "**Storm drain inlet**" means the point of entry into the storm sewer system.
- v. "**Stormwater**" means water resulting from precipitation (including rain and snow) that runs off the land's surface, is transmitted to the subsurface, is captured by separate storm sewers or other sewerage or drainage facilities or is conveyed by snow removal equipment.
- vi. "**Stormwater facility**" means stormwater infrastructure including, but not limited to, catch basins, infiltration basins, detention basins, green infrastructure (GI), filter strips, riparian buffers, infiltration trenches, sand filters, constructed wetlands, wet basins, bioretention systems, low flow bypasses, Manufactured Treatment Devices (MTDs), and stormwater conveyances.
- vii. "**Stormwater management basin**" means a stormwater management basin as defined in N.J.A.C. 7:8.
- viii. "**Stormwater management measure**" means a stormwater management measure as defined in N.J.A.C. 7:8.
- ix. "**Stormwater runoff**" means water flow on the surface of the ground or in storm sewers, resulting from precipitation.

- x. ***“Total maximum daily load” or “TMDL”*** means a total maximum daily load formally established pursuant to Section 7 of the Water Quality Planning Act (N.J.S.A. 58:11A-7) and Section 303(d) of the Clean Water Act, 33 U.S.C. §§12512 et seq. A TMDL is the sum of individual wasteload allocations for point sources, load allocations for nonpoint sources of pollution, other sources such as tributaries or adjacent segments, and allocations to a reserve or margin of safety for an individual pollutant.

- xi. ***“Waters of the State”*** means the ocean and its estuaries, all springs, streams and bodies of surface or ground water, whether natural or artificial, within the boundaries of the State of New Jersey or subject to its jurisdiction” (see N.J.A.C. 7:9B-1.4).

List of Figures

Title	Page #
Figure 1: Borough of Roosevelt - Owned/Operated Stormwater Outfalls	13
Figure 2: Interconnections Into and From the Borough of Roosevelt	15
Figure 3: Outfall Drainage Areas	31
Figure 4: Interconnection Drainage Areas	32
Figure 5A: TMDLs (2016) by Parameter Related to Stormwater for the Borough of Roosevelt	20
Figure 5B: TMDLs (PRE-2008) by Parameter Related to Stormwater for the Borough of Roosevelt	21
Figure 6: Overburdened Communities	23
Figure 7: Impervious Areas	25
Figure 8: Non-Municipal Owned/Operated Stormwater Infrastructure in the Borough of Roosevelt	27

List of Tables

Title	Page #
Table 1: Receiving Surface Water Bodies & Water Quality Classifications	12
Table 2: Interconnections Attributes	16
Table 3: Drainage Area Attributes	18
Table 4: TMDLs and Impairments for HUC 14s within or bordering the Borough of Roosevelt	19
Table 5: Non-municipally Owned or Operated Stormwater Facilities	28

Acknowledgements

The Borough of Roosevelt Watershed Inventory Report has been prepared by:



Roberts Engineering Group, LLC
1670 Whitehorse Hamilton Square Road
Hamilton, NJ 08690
www.RobertsEngineeringGroup.com
(609) 586-1141

Regional Collaboration

No regional collaboration occurred during the preparation of this report.

The Borough anticipates collaborating with the Stormwater Program Coordinators of the Township of Millstone, the Township of Upper Freehold and other municipalities to develop and implement solutions to decrease or eliminate current or potential stormwater issues on a regional and state basis.

Introduction

- **Location**

- The Borough of Roosevelt is located in western Monmouth County, having the Township of Millstone (Monmouth County) to the north, east, and southeast and the Township of Upper Freehold (Monmouth County) to the southwest. The Assunpink Creek and Assunpink Wildlife Management Area borders along the entire southern border and a portion to the east. The Borough encompasses 1.95 square miles or 1,246.5 acres.

The Borough's Municipal Office address is: 33 North Rochdale Avenue, Roosevelt, New Jersey 08555.

- Township of Millstone (Monmouth County), Township of Upper Freehold (Monmouth County) and East Windsor (Mercer County) discharge to the same subwatersheds as the Borough of Roosevelt.

- **Population**

- As per the 2020 US census, the population of the Borough of Roosevelt was 808.

- **Demographics**

- As per the 2020 US census, there were 808 Borough of Roosevelt residents, and the median age was 38.8 years. The 2020 Census notes, 650 (80.4%) identified as White, 103 (12.7%) as Hispanic or Latino (of any race), 31 (3.8%) as Black or African American, 12 (1.5%) as Asian, 1 (0.12%) as American Indian and/or Alaska Native, 0 (0.0%) as Native Hawaiian and Other Pacific Islander. Additionally, 630 (78.0%) residents identified as Not Hispanic or Latino, 32 (4.0%) as Some Other Race, and 82 (10.1%) as Two or More Races.

Out of a total of 376 households (361 occupied) in the Borough, 242 (67.0%) reported as married couples, 34 (9.4%) as a male householder without spouse or partner, and 70 (19.4%) as a female householder without spouse or partner. Of the 361 households, 113 (31.1%) were reported with individuals under 18 years old and 67 (18.4%) reported with individuals 65 years or older.

Out of a total of 376 housing units in the Borough, 361 (96.0%) of units were occupied with 82.5% as home ownership and 15 (4.0%) were vacant.

- **Land use type(s)**

- The Borough is comprised of approximately 18% urban land uses according to NJDEP GIS (Land Cover-2015). Urban land is comprised of lands that are not agricultural, forest, barren or wetlands. Approximately 91.0% (1,134.3 Ac.) of the Borough's land use is comprised of residential properties. The Borough has 3 residential zones consisting of the R-40 (40,000 sf), R-100 (100,000 sf) and R-AG400 (10 acres). Although the residential zones encompass 91.0% of the Borough and would be considered urban land use, the Borough is actually an agricultural use. The R-AG400 (10 acres) comprises 52.3% of the Borough's overall area. All the residential lots, based on their maximum lot coverage, contribute 16.2% of maximum impervious coverage. The residential units range from 1 to 2 ½ stories. In addition to residential development, urban land includes commercial, industrial, recreational and transportation use which is approximately 6.6%. The overall maximum impervious area is 22.8%.

- **Subwatersheds within or bordering the Borough of Roosevelt**

- The Borough lies within three (3) subwatersheds and two Watershed Management Areas (WMA).

Assunpink Creek (above Assunpink Lake) HUC14 02040105230010
Watershed: Assunpink Creek (above Shipetaukin Ck)
Central Delaware WMA #11

Rocky Brook (above Monmouth Co line) HUC14 02030105100040
Watershed: Millstone River (above Carnegie Lake)
Millstone River WMA #10

Rocky Brook (below Monmouth Co line) HUC14 02030105100050
Watershed: Millstone River (below Carnegie Lake)
Millstone River WMA #10

The majority of the Borough lies within the Assunpink Creek (above Assunpink Lake) subwatershed.

- **Area(s) Prone to Flooding**

- The Borough does not experience flooding with the exception of the area on Pine Drive at the wastewater treatment plant.

- **Goal for the Watershed Improvement Plan**

- Involve the community with the decision-making process of this plan via public meetings and stakeholder (Borough stormwater coordinator, Borough and County engineer, environmental commission, elected official, etc.) engagement;
- Reduce flood damage, including damage to life and property;
- Minimize, to the extent practical, any increase in stormwater runoff from any new development;
- Reduce soil erosion from any development or construction project;
- Assure the adequacy of existing and proposed culverts and bridges, and other in-stream structures;
- Maintain or improve groundwater recharge;
- Prevent, to the greatest extent feasible, an increase in nonpoint source pollution;
- Maintain the integrity of stream channels for their biological functions, as well as for drainage;
- Minimize pollutants in stormwater runoff from new and existing development in order to restore, enhance, and maintain the chemical, physical, and biological integrity of the waters of the State, to protect public health, to safeguard fish and aquatic life and scenic ecological values, and to enhance the domestic, municipal, recreational, industrial and other uses of water;
- Encourage incorporation of Low Impact Development Strategies into new and future site development plans, to ensure nonstructural stormwater management requirements are met; and

- Protect public safety through the proper design and operation of stormwater management basins.

Electronic data required for submission: None required for this section.

Public Participation

Required semiannual meetings or sessions pertaining to the Watershed Improvement Plan will be held starting in early 2026. The first meeting, consisting of the Borough's stormwater coordinator, Council, Environmental Commission and others, will discuss the contents of this report, future phases of the Watershed Improvement Plan, and begin to assemble a list of stakeholders. All Watershed Improvement Plan information, including upcoming meeting dates & times (once scheduled), will be posted on the Borough's stormwater management webpage:

[The Official Website of The Borough of Roosevelt, NJ - Stormwater Management](#)

<https://www.rooseveltnj.us/pages/stormwater-management>

Electronic data required for submission: None required for this section.

Stormwater Outfall(s)

Stormwater Outfalls Owned/Operated by Permittee

- The Borough Engineer has utilized a Global Position System (GPS) to create the MS4 Stormwater Outfall Map, which identifies the location of all outfall pipes operated by the Borough of Roosevelt and is posted on the Borough website.
- The Borough owns and operates fourteen (14) outfalls.
- All fourteen (14) outfalls discharge to the Assunpink Creek (above Assunpink Lake).

Receiving Surface Waters

- Receiving surface waters within the Borough were obtained through the NJDEP's NJ-WET GIS service. This data was obtained in December 2025 and is publicly available.
- The following surface waters are within or border the Borough of Roosevelt:
 - Assunpink Creek
 - Empty Box Brook, a tributary of Assunpink Creek
- All fourteen (14) outfalls discharge to three tributaries of Assunpink Creek.

Water Quality Classifications


- Water quality classification of receiving surface waters within the Borough were obtained through the NJDEP's NJ-WET GIS service. This data was obtained in December 2025 and is publicly available.
- All tributaries and Assunpink Creek have a water quality of FW2-NT.
- All fourteen (14) outfalls have a water quality classification of FW2-NT.

Table #1: Receiving Surface Water Bodies & Water Quality Classifications

Local Outfall ID	Receiving Surface Water Body	Water Quality Classification
1007	Assunpink Creek (Tributary)	FW2-NT
1010	Assunpink Creek (Tributary)	FW2-NT
1024	Assunpink Creek (Tributary)	FW2-NT
1028	Assunpink Creek (Tributary)	FW2-NT
1039	Assunpink Creek (Tributary)	FW2-NT
1045	Assunpink Creek (Tributary)	FW2-NT
1050	Assunpink Creek (Tributary)	FW2-NT
1054	Assunpink Creek (Tributary)	FW2-NT
1076	Assunpink Creek (Tributary)	FW2-NT
1087	Assunpink Creek (Tributary)	FW2-NT
1095	Assunpink Creek (Tributary)	FW2-NT
1098	Assunpink Creek (Tributary)	FW2-NT
1102	Assunpink Creek (Tributary)	FW2-NT
1104	Assunpink Creek (Tributary)	FW2-NT

Electronic data required for submission: None required for this section.

Figure #1: Borough of Roosevelt - Owned/Operated Stormwater Outfalls



 <p>Roberts ENGINEERING GROUP LLC <i>Women Business Enterprise Certified</i></p>	<p>FIGURE No. 1 BOROUGH OF ROOSEVELT - OWNED/OPERATED STORMWATER OUTFALLS Borough of Roosevelt, Monmouth County, New Jersey</p>	
	<p>SCALE: 1" = 1,500'± REF: NJDEP GIS NJ Watershed Eval. Tool</p>	<p>DWG. No: FIGURES DATE: December 31, 2025</p>

Stormwater Interconnection(s)


Interconnections from the Borough's MS4 into another entity's storm or sanitary sewer system

- Interconnections from the Borough's MS4 into another entity data were obtained by the Borough Engineer utilizing a Global Position System (GPS) to locate the inlets. Maintenance, inspection records and field checks through to 2025 supplement information on each inlet. The locations are publicly available via the Stormwater Facilities Map (MS4 Infrastructure Map) on the Borough stormwater webpage. There are no connections to a sanitary sewer.
- There is one (1) interconnections from the Borough's MS4 into a Monmouth County section of stormwater piping situated along County Route No. 571 (North Rochdale Avenue) and south of Oscar Drive. The interconnection is a pipe to a County owned inlet.
- There are no other interconnections to another entity's storm or sanitary sewer system.

Interconnection(s) into the permittee's MS4 from another entity

- Interconnections into the Borough's MS4 from another entity data were obtained by the Borough Engineer utilizing a Global Position System (GPS) to locate the inlets. Maintenance, inspection records and field checks through to 2025 supplement information on each inlet. The locations are publicly available via the Stormwater Facilities Map (MS4 Infrastructure Map) on the Borough's stormwater webpage.
- There are no interconnection into the Borough's MS4.
- There are no public complexes into the Borough's MS4.

Figure #2: Interconnections into and from the Borough of Roosevelt



Electronic data required for submission: Interconnections.

Data submitted with the MS4 Infrastructure Map.

Table #2: Interconnections Attributes

Local ID	Type	Upstream Entity	Downstream Entity
1118	Pipe	Borough of Roosevelt	Monmouth County

Drainage Area(s) for Stormwater Outfalls and Stormwater Interconnections

Storm Drain Inlets

- Storm drain inlet data was obtained by the Borough Engineer utilizing a Global Position System (GPS) to locate the inlets. Maintenance, inspection records and field checks through to 2025 supplement information on each inlet. The locations are publicly available via the Stormwater Facilities Map (MS4 Infrastructure Map) on the Borough's stormwater webpage.
- The Borough of Roosevelt owns and operates 85 storm drain inlets. There are 12 inlets owned by the County of Monmouth. A private stormwater system has no inlets but consists of one manhole and two sections of 18" CMP connecting to the municipal system.

No additional data required for storm drain inlets beyond what is required for the MS4 Infrastructure Map.

MS4 Outfall Drainage Areas

- Outfall drainage area data was obtained by the Borough Engineer utilizing a Global Position System (GPS) to locate the outfalls and pipes. Maintenance, inspection records and field checks through to 2025 supplement information on each inlet. The locations are publicly available via the Stormwater Facilities Map (MS4 Infrastructure Map) on the Borough's stormwater webpage.

The topography and the structures are positioned in the NJSP and provide a comparable analysis. The individual outfall drainage areas were delineated using the Autodesk Civil 3d Catchments Analyze module by calculating the proximity and catchment to the individual storm sewer system connecting to the Borough's individual designated outfall.

The topography is from the 2014 USGS CMGP Lidar: Post Sandy (Long Island, NY) at:

[2014 USGS CMGP Lidar: Post Sandy \(Long Island, NY\) | InPort](#)

Drainage area of interconnection(s) from the permittee to another entity

- Drainage area data was obtained by the Borough Engineer utilizing a Global Position System (GPS) to locate the outfalls and pipes.

The topography and the structures are positioned in the NJSP and provide a comparable analysis. Individual interconnection drainage areas were delineated using the Autodesk Civil 3d Catchments Analyze module calculating the proximity and catchment to the individual storm sewer system connecting to the designated interconnection.

The topography is from the 2014 USGS CMGP Lidar: Post Sandy (Long Island, NY) at:

[2014 USGS CMGP Lidar: Post Sandy \(Long Island, NY\) | InPort](#)

Figure #3: Outfall Drainage Areas. Please see Appendix.

Figure #4: Interconnection Drainage Areas. Please see Appendix.

Electronic data is required for submission: MS4 Outfall and Interconnection Drainage Areas.

Table #3 Drainage Area Attributes

Drainage Area ID	Drainage Area sqft/acres	Interconnection or Outfall	Primary Contributing Drainage Area Type
1007	174,442 sf / 4.0 acres	Pipe	Residential
1010	765,569 sf / 17.5 acres	Outfall 1010	Residential
1024	1,147,650 sf / 26.3 acres	Outfall 1024	Residential
1028	292,296 sf / 6.7 acres	Outfall 1028	Residential
1039	2,980,245 sf / 68.4 acres	Pipe	Residential
1045	586,015 sf / 13.4 acres	Outfall 1045	Residential
1050	268,884 sf / 6.1 acres	Outfall 1050	Residential
1054	47,297 sf / 1.1 acres	Outfall 1054	Residential
1076	843,420 sf / 19.4 acres	Outfall 1076	Residential
1087	515,027 sf / 11.8 acres	Pipe	Residential
1095	360,107 sf / 8.2 acres	Outfall 1095	Residential
1098	145,056 sf / 3.3 acres	Outfall 1098	Residential
1102	791,171 sf / 18.1 acres	Pipe	Residential
1104	262,141 sf / 6.0 acres	Pipe	Residential
1118	267,601 sq ft / 6.1 acres	Interconnection from	Residential

TMDLs and Water Quality Impairments

- The TMDLs and water quality impairments relevant to the Borough were obtained through the NJDEP’s TMDL Lookup Tool, the 303(d) List within New Jersey’s Integrated Water Quality Assessment Reports, and the NJ-WET GIS service. Subwatersheds (HUC 14s) within or bordering the Borough were identified through the NJDEP’s NJ-GeoWeb GIS service. The data was obtained in December 2025 from these sources.
- The Borough lies within three (3) subwatersheds and two Watershed Management Areas (WMA) WMA.

Assunpink Creek (above Assunpink Lake) HUC14 02040105230010
Watershed: Assunpink Creek (above Shipetaukin Ck)

Rocky Brook (above Monmouth Co line) HUC14 02030105100040
Watershed: Millstone River (above Carnegie Lake)

Rocky Brook (below Monmouth Co line) HUC14 02030105100050
Watershed: Millstone River (below Carnegie Lake)

The majority of the Borough lies within the Assunpink Creek (above Assunpink Lake) subwatershed.

- There were no TMDLs found in the three watersheds with the Borough after 2016. Rocky Brook (below Monmouth Co line) had Mercury recorded in 2020 under Sublist 4A. According to Sublist 4 and Sublist 4A, *one or more designated uses are Not Supported or are threatened but TMDL development is not required and a TMDL has been completed for the parameter causing designated use non-support, respectively.*

However, the Borough is not within a Regional Stormwater Management Planning Area (RSWMP) and no TMDLs have been developed for waters within the Borough to date; If any RSWMPs or TMDLs are developed during the program, this Watershed Inventory Report will be updated.

Table #4: TMDLs and Impairments for HUC 14s within or bordering the Borough of Roosevelt

HUC 14	Subwatershed Name	TMDL(s)	Impairment(s)
02040105230010	Assunpink Creek (above Assunpink Lake)	Phosphorus (2012)	E. coli (2012)
02030105100040	Rocky Brook (above Monmouth Co line)	Phosphorus (2016)	
02030105100050	Rocky Brook (below Monmouth Co line)	Total Suspended Solids (2016)	Dieldrin in Fish Tissue (2018), DO (2010), PCB in Fish Tissue (2012), Mercury (2020) (amended 4A)

Electronic data required for submission: None required for this section.

Figure #5A: TMDLs (2016) by Parameter Related to Stormwater for the Borough of Roosevelt





Figure #5B: TMDLs (PRE-2008) by Parameter Related to Stormwater for the Borough of Roosevelt




Overburdened Communities

This section should detail the following information for overburdened communities within the permittee's jurisdiction:

- Overburdened communities (OBC) data was obtained through the NJDEP's NJ-WET GIS service. The data was obtained in December 2025 and is publicly available.
- An area of a municipality is defined as an OBC if it meets at least one of these three criteria according to the most recent US Census:
 1. At least 35 percent of the households qualify as low-income households (at or below twice the poverty threshold);
 2. At least 40 percent of the residents identify as minority or as members of a State recognized tribal community; or
 3. At least 40 percent of the households have limited English proficiency (without an adult that speaks English "very well").
- There are no overburdened communities present in three subwatersheds located in the Borough of Roosevelt.
- In maintaining the non-overburdened status, the Borough is very diligent in pursuing any County, State and Federal funding for improvements to roadways and infrastructure including Borough recreational areas and parks. There are several recently completed and pending roadway improvement projects and park upgrades.

Electronic data required for submission: None required for this section.

Figure #6: Overburdened Communities within the Borough of Roosevelt



Overburdened Communities under the New Jersey Environmental Justice Law

- | | |
|--|---|
| <ul style="list-style-type: none"> Overburdened Communities Municipality Watersheds (DEPHUC14) | <p>SUBWATERSHEDS:</p> <ul style="list-style-type: none"> ① ASSUNPINK CK (ABOVE ASSUNPINK LAKE) 02040105230010 WATERSHED: ASSUNPINK CREEK (ABOVE SHIPETAUKIN CK) ② ROCKY BROOK (ABOVE MONMOUTH CO LINE) 02030105100040 WATERSHED: MILLSTONE RIVER (ABOVE CARNEGIE LAKE) ③ ROCKY BROOK (BELOW MONMOUTH CO LINE) 02030105100050 WATERSHED: MILLSTONE RIVER (ABOVE CARNEGIE LAKE) |
|--|---|



Roberts
ENGINEERING GROUP LLC
Women Business Enterprise Certified

FIGURE No. 6
OVERBURDENED COMMUNITIES
WITHIN THE BOROUGH OF ROOSEVELT
Borough of Roosevelt, Monmouth County, New Jersey

SCALE: 1" = 1,500'±
REF: NJDEP GIS NJ Watershed Eval. Tool

DWG. No: FIGURES
DATE: December 31, 2025

Impervious Area

- Data set entitled Monmouth County Impervious Surface (2015) of New Jersey, NJ-WET and the Borough Zoning Map for residential, commercial and industrial districts were used to determine the impervious coverages of the Borough. The impervious area was determined using the allowable maximum impervious coverage for each zone.
- The percent impervious cover in each subwatershed within the Borough of Roosevelt is:

Assunpink Creek (above Assunpink Lake) HUC14 02040105230010: 20.4% Impervious


Rocky Brook (above Monmouth Co line) HUC14 02030105100040: 2.2% Impervious

Rocky Brook (below Monmouth Co line) HUC14 02030105100050: 0.2% Impervious
- An Impervious cover is any surface that does not allow water to infiltrate into the ground and reach groundwater. Roadway and parking areas (excluding pervious pavement), concrete pads, sidewalks and recreational surfaces like tennis and basketball do not allow direct infiltration to the subsurface for plants and groundwater recharge. The impervious cover generates stormwater runoff which affects the hydrological cycle and water quality. Stormwater that would naturally seep into the soil is redirected elsewhere and thus reducing groundwater recharge. Stormwater runoff transports nitrogen, phosphorus, fecal coliform, total suspended solids, trash and other pollutants directly to the waterways. These pollutants cause significant harm to the ecosystems of the waterways by compromising the water quality, potential algal blooms and bioaccumulation of pollutants in fish.

Providing more pervious land in large areas of impervious cover using Green Infrastructures like vegetative buffers and maintaining established green areas is essential to the health of local watersheds.

Electronic data required for submission: None required for this section.

Figure #7: Impervious Area within the Borough of Roosevelt




 <p>Roberts ENGINEERING GROUP LLC <i>Women Business Enterprise Certified</i></p>	<p>FIGURE No. 7 IMPERVIOUS AREAS WITHIN THE BOROUGH OF ROOSEVELT Borough of Roosevelt, Monmouth County, New Jersey</p>	
	<p>SCALE: 1" = 1,500'± REF: NJDEP GIS NJ Watershed Eval. Tool</p>	<p>DWG. No: FIGURES DATE: December 31, 2025</p>

Non-Municipally Owned or Operated Stormwater Facilities *(for Tier A permittees only)*

- Non-municipally owned or operated stormwater facility data was researched/obtained through the Rutgers University H&H and NJDEP Land Use Land Cover 2020 datasets. Filed records with the Borough Engineer were also reviewed for any non-municipally owned or operated facilities not referenced in those datasets. Data was researched/obtained in December 2025.
- According to the Rutgers University H&H, no non-municipal owned or operated stormwater facilities are found in the Borough. The Borough has no facilities on record.

Figure #8: Non-municipally Owned/Operated Stormwater Infrastructure in the Borough of Roosevelt



Electronic data required for submission: Non-municipally Owned/Operated Stormwater Infrastructure.

Table #5: Non-municipally Owned or Operated Stormwater Facilities

Block	Lot	Facility Type	Subwatershed	Property Owner	Map Number
		None			

Conclusion

The Watershed Inventory Report, Phase 1 of the Watershed Improvement Plan, identifies stormwater infrastructure, as required in the MS4 permits. It also summarizes water quality data, including stream classifications, TMDLs, and water quality impairments. The data that accompanies this inventory report has been compiled as an electronic map and submitted to the NJDEP through NJDEP Online via the Stormwater Document Submittal Service. The information from this inventory report will be used to make informed decisions during the creation of the Watershed Assessment Report, Phase 2 of the Watershed Improvement Plan. The work done in Phase 2 will identify areas of potential concern and where potential water quality improvement projects may be implemented to address the highlighted water quality and quantity issues identified in this inventory report.

References

Data Sources

2020 Census of Population and Housing. Retrieved on Month Day, Year from U.S. Department of Commerce, U.S. Census Bureau website: <https://data.census.gov/>.

New Jersey 2022 Integrated Water Quality Report, including the 303(d) Impaired Waters List. Retrieved on Month Day, Year from New Jersey Department of Environmental Protection, Bureau of Bureau of Environmental Analysis, Restoration and Standards website: <https://dep.nj.gov/wms/bears/integrated-wq-assessment-report-2022/>.

New Jersey Watershed Evaluation Tool (NJ-WET). Retrieved on Month Day, Year from Division of Watershed and Land Management, Bureau of NJPDES Stormwater Permitting website: <https://dep.nj.gov/njpdessstormwater/municipal-stormwater-regulation-program/watershed-improvement-plan-guidance/>.

NJDEP Open Data. Retrieved on Month Day, Year from Division of Information Technology, NJDEP Bureau of GIS website: <https://gisdata-njdep.opendata.arcgis.com/>.

Total Maximum Daily Load (TMDL) Look-Up Tool. Retrieved on Month Day, Year from New Jersey Department of Environmental Protection, Bureau of NJPDES Stormwater Permitting website: <https://dep.nj.gov/njpdessstormwater/municipal-stormwater-regulation-program/tmdl/>.

New Jersey Hydrologic Modeling (H&H) Database. Retrieved on May 30, 2025 from Rutgers University Hydro website: <https://hydro.rutgers.edu/>.

Appendix

Figure #3: Outfall Drainage Areas

Figure #4: Interconnection Drainage Areas

Figure #3: Outfall Drainage Areas



Figure #4: Interconnection Drainage Areas

